



ADDENDUM No. 2

Project Name: Veterans Memorial Park Pickleball Courts

MJ Project No: 965.19

Addendum Date: July 7, 2023

To: All Plan Holders of Record

This addendum forms a part of the Contract Documents and modifies the original Drawings and Specifications dated June 15, 2023. All contract bidders must acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the bidder to disqualification.

Contract Drawings:

1. Drawing C-500 Details:

- a. Detail 3 Pickleball Court Surfacing Section: Replace note that reads “EXISTING 6” COMPACTED $\frac{3}{4}$ ” CRUSHED STONE. STONE TO BE RE-COMPACTED. PROVIDE ADDITIONAL STONE FOR SHIM TO ESTABLISH LEVEL SURFACE” with “PROVIDE 8” SUBBASE TYPE 2”.
- b. Detail 4 Asphalt Pavement Section: Replace note that reads “EXISTING 6” COMPACTED $\frac{3}{4}$ ” CRUSHED STONE. STONE TO BE RE-COMPACTED. PROVIDE ADDITIONAL STONE FOR SHIM TO ESTABLISH LEVEL SURFACE” with “PROVIDE 8” SUBBASE TYPE 2”.
- c. Detail 9 Pickleball Court: Add note that reads “8. Basis of design manufacturer is Bison Incorporated model PK10LX Competition Pickleball System with indoor/outdoor competition net and ground sockets/cover plates.”

Specifications:

2. Section 323113 Chain Link Fences and Gates:

a. Section 2.3 Fence Framework, add the following:

- “2. Light-Industrial-Strength Material: round steel pipe. Line Post: 1.9 inches in diameter. End, Corner, and Pull Posts: 4.0 inches in diameter.
3. Horizontal Framework Members: Top rails according to ASTM F1043. 1.625 inches in diameter.

4. Polymer coating over metallic coating. Color black according to ASTM F934.”

Clarifications:

3. It is the intent of the project to only provide conduit and pull string for future electrical work by others. Location and size of conduit shown on Sheet C-150.

END OF ADDENDUM