

ADDENDUM NO. 2 TO:
Settler's Hill Trail Reconstruction Project

IN THE LETTING OF
June 29, 2023

TRANSMITTAL MEMO

This amendment was initiated by the Town of Clifton Park to make clarifications to the contract documents based on questions received from potential bidders:

1. Are there any liquidated damages associated with the completion timeline?

As long as the selected contractor is working in good faith and delays are outside of their control (i.e., weather-related), no liquidated damages will be assessed for outside the 75-day window unless such issues relate to negligence or mismanagement resulting in breaching the timeline.

2. I do not see sheet II-5 in the bid manual for completion? Can you confirm if there is a sheet to be included in the bid submission?

Sheet II-5 is in the manual, but the page was placed out of order. Please see page 58 of the PDF. A copy of Sheet II-5 is also attached to this addendum.

3. Is there a specific bid bond form to be used for this project? It does not look like one was included, or is a standard AIA acceptable?

The Town of Clifton Park accepts a standard AIA form as the specified bid bond form.

4. Will retainage be held on this project? If so, what percentage?

Retainage will not be held on this project due to the Town's desire to complete the work promptly within the prescribed construction timeline. Payments will be processed based on the quality of the work completed and agreed-upon metrics within the payment request (i.e., linear feet repaired per the contract).

5. Does the trail reconstruction end at the limit of damaged asphalt, or is it the entire length of trail?

As per the Project Limit Map in the bid manual (page 67 of the PDF), trail reconstruction begins at Wallflower Dr and ends at Miller Rd. The entire trail is to be replaced within those limits. Cross section of proposed trail is on page 68 of pdf. The trail will be 8' wide.

PLEASE BE GOVERNED ACCORDINGLY WHEN SUBMITTING BIDS

Project: Settler's Hill Trail Reconstruction

Proposal Line Number	Item ID Description	Bid Req. Code	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0002	203.02 UNCLASSIFIED EXCAVATION AND DISPOSAL		1,490.0 CY	_____.	_____.	_____.	_____.
0004	203.03 EMBANKMENT IN PLACE		400.0 CY	_____.	_____.	_____.	_____.
0006	207.24 GEOTEXTILE STABILIZATION		3,570.0 SY	_____.	_____.	_____.	_____.
0008	209.13 SILT FENCE-TEMPORARY		2,000.0 LF	_____.	_____.	_____.	_____.
00010	304.12 SUBBASE COURSE, TYPE 2		595.0 CY	_____.	_____.	_____.	_____.
00012	608.020102 ASPHALT SIDEWALKS, DRIVEWAYS AND BICYCLE PATHS,AND VEGETATION CONTROL STRIPS		540.0 TON	_____.	_____.	_____.	_____.
00014	610.16010020 TURF ESTABLISHMENT - PERFORMANCE		2,973.0 SY	_____.	_____.	_____.	_____.
00016	619.01 BASIC WORK ZONE TRAFFIC CONTROL		1.0 LS	_____.	_____.	_____.	_____.
00018	620.03 STONE FILLING (LIGHT)		120.0 CY	_____.	_____.	_____.	_____.
00020	623.12 CRUSHED STONE (IN-PLACE MEASURE)		120.0 CY	_____.	_____.	_____.	_____.
00022	627.50140008 CUTTING PAVEMENT		20.0 LF	_____.	_____.	_____.	_____.
00024	697.03 FIELD CHANGE PAYMENT		29,100 DC	1.00		29,100.00	

Proposed Total Bid: _____.