

ADDENDUM NO. 1

Project Name: Town of Clifton Park

Dutch Meadows Sewer District Pump Station Upgrades

Engineer Project No: MJ965.14

Addendum Date: December 11th, 2025

To: All Contract Bidders of Record

This addendum forms a part of the Contract Documents. All contract bidders must acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the bidder to disqualification.

The scope of work provided in the Contract Documents has been amended as follows:

CHANGES TO THE SPECIFICATIONS

1. Revise Section 001113 labeled “Advertisement for Bids”, where, in the first paragraph, the bid opening is listed out as “Wednesday, December 17th, 2025 at 2:00PM”. The **bid opening** date and time are now the following: “**Thursday, December 18th, 2025 at 2:00PM.**”

RESPONSES TO QUESTIONS FROM BIDDERS

1. Question #1: Are the existing pumps explosion proof?
 - a. Answer #1: Yes, the existing pumps at each pump station are explosion proof. Replacement of the existing pumps is **not** a part of the project scope.
2. Question #2: Should pump rail lift-out system be non-sparking?
 - a. Answer #2: Yes, the pump rail lift-out system shall be of non-sparking design. Refer to Section 460710 Part 2.01 Paragraph A in the specifications for more information.
3. Question #3: Should I include intrinsically safe relays for controls?
 - a. Answer #3: Yes. Refer to Section 460710 Part 2.05 Paragraph H in the specifications for more information.
4. Question #4: How long can pump stations remain on bypass?
 - a. Answer #4: Town requires an estimated bypass timeline from the contractor for their review and approval. Town has capabilities of bypassing each pump station one at a time indefinitely, however will approve all reasonable bypassing requests up to their discretion.

End of Addendum No. 1